



Avinashilingam Institute for Home Science and Higher Education for Women

(Deemed to be University under Category 'A' by MHRD, Estd. u/s 3 of UGC Act 1956)

Re-accredited with 'A' Grade by NAAC. Recognised by UGC Under Section 12 B

Coimbatore - 641 043, Tamil Nadu, India

Sealed tenders are invited from approved contractors till 3.00p.m.on 28.01.2019 for the following work in Avinashilingam Institute for Home Science and Higher Education for Women, Coimbatore - 641 043.

S. No	Name of Work	Estimate Cost	Tender Cost	E.M.D	Tender issue from	Tender Submission
1	Providing bituminous road and Paver block stones for playground at campus-II	Rs.12,34,000/-	Rs.6,000/- +G.S.T	1% of quoted value	12.01.2019 to 28.01.2019	28.01.2019 at 3.00 PM

Documents and other particulars can be downloaded from 12.01.2019 in this website www.avinuty.ac.in. the cost of tender document should also be enclosed at the time of tender submission. The D.D. for tender cost and E.M.D may be drawn in favour of "The Registrar, Avinashilingam Institute for Home Science and Higher Education for Women, Coimbatore - 641043"


REGISTRAR

**AVINASHILINGAM INSTITUTE FOR HOMESCIENCE AND HIGHER
EDUCATION FOR WOMEN,
COIMBATORE – 641 043**

Sealed Tenders are invited for the under mentioned work.

Name of the work: Providing bituminous road and Paver block stones for playground at campus-II of Avinashilingam Institute for Home science and Higher Education for Women, Coimbatore - 641043.

Completion period: 30 Days.

Name of the Contractor

Address of the contractor

.....

.....

.....

.....

Tender conditions - 5 Pages
Price Bid -4 Pages

**AVINASHILINGAM INSTITUTE FOR HOMESCIENCE AND HIGHER
EDUCATION FOR WOMEN,
COIMBATORE – 641 043**

Sealed Tenders are invited for the under mentioned Work.

Name of Work : Providing bituminous road and Paver block stones for playground at campus-II of Avinashilingam Institute for Home science and Higher Education for Women, Coimbatore - 641043.

Completion Period : 30 Days.

Tender receiving Authority : THE REGISTRAR,
AVINASHILINGAM INSTITUTE FOR HOMESCIENCE
AND HIGHER EDUCATION FOR WOMEN,
COIMBATORE – 641 043.

Date & Time for Tender

Opening : 28.01.2019, 3:30 pm

E.M.D. Amount : 1% of the quoted value

Sealed Tenders (PRICE BID) are to be submitted in person in the cover containing the name of the work on the cover

The undersigned reserves the right to reject the lowest or any of all the tenders or to accept any tender wholly or in part or parts without assigning the reason whatsoever thereof.

REGISTRAR

**AVINASHILINGAM INSTITUTE FOR HOME SCIENCE AND
HIGHER EDUCATION FOR WOMEN COIMBATORE – 641 043**

TERMS AND CONDITIONS

Name of the Work: Providing bituminous road and Paver block stones for playground at campus-II of Avinashilingam Institute for Home science and Higher Education for Women, Coimbatore – 641043.

1. Sealed tenders will be received for the above work by The Registrar Avinashilingam Institute for Home science and Higher Education for Women, Coimbatore - 641 043 up to 3:00 pm on 28.01.2019.
2. The tenders should be in the prescribed form obtainable from The Registrar, Avinashilingam Institute for Home science and Higher Education for Women, Coimbatore - 641 043.
3. Tenders – must be submitted in sealed covers and should be addressed to **“The Registrar, Avinashilingam Institute for Home science And Higher Education for Women, Coimbatore – 43”**.
4. 1% E.M.D. amount on quoted value should be enclosed with the tender document in the form of Demand draft.
5. In case of the successful Tenderer, the amount of E.M.D will be deposited towards “Security Deposit” for entire contract period, including defects liability period. In addition to the above, the selected contractor shall deposit further amount of 1% in the form of Demand draft towards security deposit so that the total security deposit amounts to 2% of the contract value. The above security deposit shall be refunded on satisfactory completion of the defects liability period and shall not carry any interest.

6. 5 % of the value of work done will be deducted in each bill of payment as withheld amount. The withheld amount and Security deposit so deducted will be refunded after defects liability period. The defects liability period shall be six months from the date of completion of works.
7. If the contractor fail to rectify the defects during the above period of six months, after getting due notice from **The Registrar** such defects will be rectified by the another contractor and the amount will be adjusted from the Withheld amount.
8. **The Registrar** reserves the right to reject any or all the tenders Without assigning any reason thereof.
9. The work should be completed within the stipulated time.
10. The taxes will be deducted as per the Government rules in each and every bill payable to the contractor. (Present rate Income tax - 2%, and Labour welfare fund – 1%)
11. Before handing over the work on completion, the contractor should clean up the entire site at his own cost.
12. The Tenderer should carefully go through the tender schedule and quote their rates for all items plus G.S.T separate.
13. The rates should be filled in figures neatly taking into account the metric units specified in the tender. Scribbling, over-writings and erasing should be avoided as far as possible. Each and every Erasing, over writing if any should be initialed.
14. The amount of each items of work should be worked out with proper care.
15. The Tenderer submitted without filling up the tender forms are liable to be rejected.
16. The work shall be carried out in the best workmanship manner, and best materials available in the market.

17. The entire work covered by the contract shall be maintained at the contractors risk until the contract is fulfilled and the works are taken over by **The Registrar**, Avinashilingam Institute for Home science and Higher Education for Women, Coimbatore – 43.
18. Use the following branded **Cement** - Chettinad, ACC, Coromandel & Ramco
19. During the execution if any damage made by the contractors in the existing pipe line, sewage line, telephone cable and electricity cables etc., has to be rectified @ their own cost.
20. The contractor shall be responsible for all injury to person, animals or things, and for all structural and decorative damage to property which may arise from the operation or neglect of himself or of any nominated sub – contractor’s employees, whether such injury or damage arise from carelessness, accident or any other cause whatever in any way connected with the carrying out this contract.
21. The work should be completed within 30 days.

REGISTRAR

AVINASHILINGAM INSTITUTE FOR HOME SCIENCE AND HIGHER EDUCATION FOR WOMEN, COIMBATORE - 43

Providing bituminous road and Paver block stones for playground at campus-II

Price Bid

S.I No	Description of works	Quantity	Rate in figures	Rate in words	Per	Amount
1	Earth work excavation in all and soil up to a depth of 0.20m including the cost of cutting and conveyance of Excavated earth within the campus including all labour charges loading and unloading etc. complete.	277.00 m ³			m ³	
2	Granular Sub-base with Graded Meterial (Table:-400-1)-point method (Construction of granular sub base by providing close graded Material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site spreading in uniform layers with motor grader On prepared surface compacting with vibratory power roller to achieve the desired Density etc. complete (asperclause401) – for grading-Material (150mm thickness)	1174.00 m ²			m ²	

3	<p>Providing and laying spreading and compacting Wet Mix Macadam with clean Crushed, graded Aggregates and granular material and finished in accordance with the Requirements from Apporved source and mixed in the specified preparation including Cost and conveyance Of all materials, stacking and mixing in the specified preparation spreading after mixing Required camber, leveling watering with all leads to obtain Moisture levels of mix between 1% above and 2% below the optimum moisture content at the time of compaction and compacting each layer with 8-10 tones power roller to obtain the required proctor density including all labour, charges for all tools and plants employed and their entire incidental charges etc. (100mm thickness)</p>	1174.00 m ²			m ²	
4	<p>Tack coat-providing and applying tack coat with bitumen emulsion (RS-I type) using emulsion pressure distributor at the rate of 6kg/10sqm on the prepared bituminous / granular surface cleaned with mechanical broom as per clause 503 over granular surface striated with primer</p>	1174.00 m ²			m ²	

5	<p>Providing and laying 30mm compacted thick semi Dense bituminous concrete using 0.10 cum of 11.2mm IRC size HBG metal 0.16 cum of 6.7 IRC size HBG metal 0.11 cum of 2.5mm below with 30kgs of (80/100) bitumen for pre mixing per 10sqm including coat and conveyance of material to CMP site heading the bitumen and aggregates to require Temperature and mixing them in central hot mix plant 40-60 tones capacity, conveying the mix by tipper trucks to site, for uniform thickness 30mm with manual laying to the specified grades and cross section and compaction by vibratory roller, bitumen into bitumen tank including hire charges and fuel charges for 40-60 MT to CMP with bitumen tools and plant required, including all other incidental charges etc, complete</p>	1174.00 m ²			m ²	
6	<p>Supplying and laying interlocking paver blocks of 80mm thick & M 30 grade with rubber moulded of laid in required line, level, curvature, colour and pattern, filling the joints with fine sand including with 100mm thickness bed of dust etc., all materials and labour charges etc., complete.</p>	65.00 m ²			m ²	

7	Supplying and laying Kerb stones of size 300mm x 100mm x 450mm in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 M. sand), including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5mm) including making drainage opening wherever required etc complete as per direction of Engineer-in-charge.	424.00 Nos			Nos	
8	Supplying and fixing of Reinforced Cement Concrete pipe size of 2'0" feet dia and 6'0" feet length with suitable concrete mixing including with all materials and labour charges etc., complete.	16.00 Nos			Nos	
9	Coursed Rubble Masonry in Cement Mortar 1:6 (One Cement and Six M. sand) by using size stones and bond stones including with all materials, labour charges and curing etc., complete.	9.00 m ³			m ³	

**Total
GST**

**Rs.
Rs.**

Rupees in words:

Contractor Signature with Seal